Serial No.	Description of work	Unit	Quantity
11	Roofing with First Class Mangalore Tiles with teak reepers 2" x 1" and chunam borders complete.	Sqr.	7·11
12	Ridge tiles set in mortar	R.ft.	16
13	Teakwood eave board 9" as per approved design ...	,,	31
14	Removing and refixing old eave board at gable ends ...	,,	48
15	Flooring with 1½' Cuddapah slabs over 3 ' concrete bed including cement pointing.	Sqr.	4·54
16	Removing the existing roof and joining with new ones ...	Item	1
17	Dismantling wall and inserting door and windows ...	,,	1
18	Painting with Chocolate silicate paint	Sqr.	3·73
19	Constructing compound wall 5 feet high with ¾ foot brick in mud pannels with 1½ feet pillaster on 1 foot foundation.	R.ft.	108
20	Providing cup boards with panelled shutters	Sq.ft.	...
	Providing additional accommodation for the Railway Dispensary, Mysore.		
1	Earthwork excavation	1,000 C.ft.	188
2	Burnt brick in mortar (foundation and basement) ...	C.ft.	432
3	Do clay superstructure	,,	505
4	Do mortar, Arch work, including centering charges.	,,	44
5	Burnt stone slabs roughly dressed 6" thick	S.ft.	70
6	Plastering with mortar	Sqr.	13·61
7	White washing	,,	13·61
8	Roofing with First Class Mangalore Tiles over 2" x 1" teak reepers.	,,	4·67
9	Ridge tiles set in mortar	R.ft.	11
10	Teakwood eave board 9" plain	,,	22
11	Teakwood door with panelled shutters including all fittings as per approved design.	S ft.	57
12	Teakwood windows with glazed shutters and iron bars with all fittings as per approved design.	,,	12
13	Teakwood wide doorway with shutters, hinges, locking arrangements, fastenings, etc., complete as per approved design.	,,	50
14	Teakwood circular ventilators with iron bars and glazed shutters.	,,	7
15	Teakwood work wrought and put up including wood oiling.	C.ft.	22·14
16	Removing and refixing teakwood eave board	R.ft.	1
17	Do do window.. ...	Each	1
18	Dismantling wall and fixing new door including plastering	No.	4
19	Drilling holes in gate pillars	,,	4
20	Painting with chocolate	Sqr.	4·13
21	Teakwood trellis work with size of reepers to be given ...	S.ft.	77
22	Removing and refixing trellis work	,,	1
23	Do verandah slabs	,,	1
24	Flooring with Cuddapah slabs over 3" concrete bed including cement pointing.	Sqr.	2·09

M. RAMAIYA,
Executive Engineer.

MYSORE SPECIAL DIVISION.

Notice dated 10th September 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, up to 10th October 1928, till 2 P.M., for collection of granite metal for metalling Chamundi Hill Road, Mysore. An approximate quantities are given below. These quantities are not guaranteed. The work should be completed by the end of February 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit	
		In words	In figures

4. Each tender must be accompanied by a deposit of Rupees one hundered and (Rs. 100) in cash or Government Promissory Notes, State Loan Bonds at market rates or in Savings Bank Pass Book of the tenderer having that amount at his credit on that date as earnest money, and be superscribed "Tender for collecting granite metal for metalling Chamundi Hill Road at Mysore" in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the Executive Engineer, Special Division, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No tender stating "percentage less than the lowest tender or as per estimated rates" will be accepted.

10. Once the tender has been accepted no claim for any concessions or higher rates will be entertained.

11. The work to be executed as per D. P. W. Specification.

12. The decision of the Executive Engineer in all matters, regarding measurements, rates, etc., shall be final and legally binding.

Abstract estimate.

No.	Items of work	Quantity	Per	Rate	
				In figures	In words
1	Collecting and stalking 1½" granite metal in 1—1, 3—1, 4—1, 5—1, 7—1, 8—1, 1—2, 2—2, 3—2, 4—2, 5—2, 8—2, 2—3, 3—3, 4—3 and 6—3 furlongs on Main Road.	1,800	Cyds.	...	...

V. V. KARVE,
Executive Engineer.

KOLAR DIVISION.

Notice dated 21st August 1928.

The attention of the Public is invited to the notification published in the *Mysore Gazette*, dated 30th August 1928, Part VI, pages 869 and 870, calling for tenders for restoring Chillaralapalli Oorumundinakere, Regd. No. 372 of Srinivaspur Taluk.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.